



**State of West Virginia
Request For Quotation
Construction**

Procurement Folder : 507450

Document Description : Addendum No. 1 North Bend SP Cabin Rehabilitation

Procurement Type : Agency Contract - Fixed Amt

Date Issued	Solicitation Closes	Solicitation No	Version	Phase
2018-10-25	2018-11-20 13:30:00	ARFQ 0310 DNR1900000048	2	Draft

SUBMIT RESPONSES TO:	VENDOR
BID RESPONSE DIVISION OF NATURAL RESOURCES PROPERTY & PROCUREMENT OFFICE 324 4TH AVE SOUTH CHARLESTON WV 25303-1228 US	Vendor Name, Address and Telephone

FOR INFORMATION CONTACT THE

James H Adkins
 (304) 558-3397
 jamie.h.adkins@wv.gov

Signature X

FEIN #

DATE

All offers subject to all terms and conditions contained in this solicitation

ADDITIONAL INFORMATION:

Addendum No.01 is issued to publish and distribute the attached information to the Vendor Community.

INVOICE TO		SHIP TO	
DIVISION OF NATURAL RESOURCES WEST VIRGINIA STATE PARKS 324 4TH AVE SOUTH CHARLESTON WV25303-1228 US		SUPERINTENDENT DIVISION OF NATURAL RESOURCES NORTH BEND STATE PARK 202 NORTH BEND PARK RD CAIRO WV 26337-9730 US	

Line	Commodity Line Description	Qty	Unit Issue	Unit Price	Total Price
1	Building maintenance and repair services				

Commodity Code	Manufacturer	Model #	Specification
72101500			

Extended Description

To make modifications and upgrades to nine (9) cabins at North Bend State Park.

SCHEDULE OF EVENTS		
Line	Event	Event Date
1	Non-Mandatory Pre-Bid Meeting at 10:00 a.m., EST	2018-11-01
2	Technical Question Deadline at 9:00 a.m., EST	2018-11-08

DNR1900000048	Document Phase Draft	Document Description Addendum No. 1 North Bend SP Cabin Rehabilitation	Page 3 of 3
----------------------	--------------------------------	---	------------------------------

ADDITIONAL TERMS AND CONDITIONS

See attached document(s) for additional Terms and Conditions

SOLICITATION NAME: ARFQ DNR19*48

North Bend State Park -Cabin Renovations

Addendum Number: 1

The purpose of this addendum is to modify the solicitation identified above to reflect the change (s) identified and described below.

Applicable Addendum Category:

- Modify bid opening date and time
- Modify specifications of product or service being sought
- Attachment of vendor questions and responses
- Attachment of pre-bid sign-in sheet
- Correction of error
- Other

Description of Modification to Solicitation:

1. **Addendum issued to provide a revised Project Manual/Specifications.**

Additional Documentation: Documentation related to this Addendum (if any) has been included herewith as Attachment A and is specifically incorporated herein by reference.

Terms and Conditions:

1. All provisions of the Solicitation and other addenda not modified herein shall remain in full force and effect.
2. Vendor should acknowledge receipt of all addenda issued for this Solicitation by completing an Addendum Acknowledgment, a copy of which is included herewith. Failure to acknowledge addenda may result in bid disqualification. The addendum acknowledgement should be submitted with the bid to expedite document processing.

Attachment A

Project Name: Cabin Modernization-North Bend State Park

WV Division of Natural Resources

Parks and Recreation Section

Cabin Modernizations

North Bend State Park

Project Manual

Project Name: Cabin Modernization-North Bend State Park

1. Project Summary

- 1.1** Project Name: North Bend State Park Cabin Modernization.
- 1.2** Location: 202 North Bend State Park Road, Cairo, WV 26337-6744
- 1.3** Agency's Name: West Virginia Division of Natural Resources (WVDNR).
- 1.4** This project generally consists of the rehabilitation and renovations of guest cabins, per the specifications outlined in this Project Manual.

Project Name: Cabin Modernization-North Bend State Park

PROJECT SCOPE OF WORK

2-bedroom cabins: Cabins #1, 4, 5, 6, 7, 8

2. Remove Existing and Replace Roof;

2.1. Replace Roofing system;

2.1.1. Vendor must supply and install all the materials to repair and replace cabin roof;

2.1.2. Vendor Must remove existing shingles to existing wood deck;

2.1.2.1. Unforeseen Damage: Vendor must inspect roof deck and must recommend to owner any necessary replacement. Bid as indicated on pricing page must include a unit price for roof deck and fascia replacement should any be necessary. No work must be performed to replace deck unless approved by the owner in writing. The unit price listed on the pricing page must be used to determine the cost to replace any necessary deck, fascia, and or framing;

2.1.3. Vendor must properly install new 1-1/2 aluminum drip edge around the perimeter of the cabin;

2.1.4. Vendor must install synthetic felt vapor barrier on roof deck;

2.1.4.1. Rhino roof U20 synthetic felt vapor barrier, or equal;

2.1.4.1.1. Thickness must be minimum 7-mils;

2.1.5. Vendor must install shingles;

2.1.5.1. Owens Corning Duration shingles, or equal;

2.1.5.1.1. Must be dimensional shingle;

2.1.5.1.2. Must have minimum 10-year algae resistance;

2.1.5.1.3. Agency must select color from manufacturer's available colors;

2.1.6. Vendor must remove wood shakes from chimney, reflash and install vinyl wood shake siding;

2.1.6.1. Norandex, Home Accents, Staggered Shake, or equal;

2.1.6.1.1. Must have fade protection warranty;

2.1.6.1.2. Agency must select color from manufacturer's available colors;

Project Name: Cabin Modernization-North Bend State Park

2.1.7. Vendor must replace chimney cap with stainless steel cap and pipe cap;

2.1.8. Vendor must install 6” seamless aluminum gutters with hidden hangers and gutter guards;

2.1.9. Vendor must install 3” x 4” downspout with drain adaptors;

2.1.10. Vendor must follow manufacturer’s recommendations for installation;

2.2. Repair Ceiling in Cabin #1

2.2.1. Remove and replace water damaged tongue and grove cedar ceiling boards around the chimney

3. Remove Existing and Replace Deck;

3.1. Site conditions may require the Vendor to change the location of the steps. Deck may require built in removable frame to access water controls;

3.1.1. Vendor must field measure and remove existing decks, including steps and ramps;

3.1.2. Vendor must provide all material necessary;

3.1.3. Vendor must rebuild deck to same size and in same configuration;

3.1.4. All lumber used must be pressure treated and rated for outdoor use, lumber that meets the ground must be rated for “Ground Contact”;

3.1.5. Footings should be installed or replaced as needed;

3.1.6. Fasteners should be compatible for use with treated lumber;

4. Remove Existing and Replace Kitchen Countertops;

4.1.1. Vendor must remove existing countertop;

4.1.2. Vendor must supply and install same size commercial grade solid kitchen countertops with center hole pre-drilled to fit specified faucet;

4.1.3. Vendor must supply and install Du Pont Corian (Formerly Zodiaq) 2020 quartz kitchen countertop or equal;

4.1.3.1.Countertop must be prepped for undermount double basin stainless steel sink;

4.1.3.2.Countertop must have flat edge;

4.1.3.3.Pattern to be selected by Agency; Must be naturally stain resistant or permanently sealed to prevent staining;

Project Name: Cabin Modernization-North Bend State Park

4.1.3.4.Countertop must be minimum of 1-1/8" thick; Flat edge;

4.1.3.5.Countertop must have minimum 4" integrated backsplash to be included and installed to existing configuration;

4.1.3.6.Vendor must field measure to ensure adequate coverage;

4.1.3.7.Vendor must follow manufacturer's recommendations for installation;

5. Remove Existing and Replace Kitchen Sink;

5.1.1. Vendor must supply and install 33-inch x 22-inch Double-basin, stainless steel undermount 2-hole sink;

5.1.1.1.Sink must be stainless steel;

5.1.1.2.Sink must be minimum 18 gauge;

5.1.1.3.Sink must be a minimum of 8" deep, maximum of 12" deep;

5.1.1.4.Sink must include basin grid;

5.1.1.5.Sink must be corrosion resistant;

5.1.1.6.All drains must be plumbed;

5.1.1.7.Sink must include all necessary hardware and installed per manufacturer's recommendations;

6. Remove Existing and Replace Kitchen Faucets;

6.1.1. Vendor must supply and install a heavy duty, high arc, kitchen faucet with spray head;

6.1.1.1. Delta 9113-AR-DST Essa, or equal;

6.1.1.1.1. Must be single handle pull down faucet;

6.1.1.1.2. Finish to be selected by Agency;

6.1.1.1.3. Faucet must have minimum flow rate of 1.80 GPM @ 60 PSI;

6.1.1.1.4. Faucet must have minimum spout height of 15-1/4";

6.1.1.1.5. Faucet must have minimum spout length of 9-1/4";

6.1.1.1.6. Faucet must have minimum deck thickness must be 2-1/2";

6.1.1.1.7. Faucet must have magnetic docking spray head;

Project Name: Cabin Modernization-North Bend State Park

6.1.1.1.8. Faucet must be installed using manufacturer's installation recommendations;

6.1.1.1.9. Faucet must be fully plumbed to hot and cold water;

PROJECT SCOPE OF WORK

3-bedroom cabins: Cabin # 2 & 3

7. Remove Existing and Replace Roof (Cabin 2 & 3);

7.1 Replace Roofing system;

7.1.1 Vendor must supply and install all the materials to repair and replace cabin roof;

7.1.2 Vendor Must remove existing shingles to existing wood deck;

7.1.2.1 Unforeseen Damage: Vendor must inspect roof deck and must recommend to owner any necessary replacement. Bid as indicated on pricing page must include a unit price for roof deck and fascia replacement should any be necessary. No work must be performed to replace deck unless approved by the owner in writing. The unit price listed on the pricing page must be used to determine the cost to replace any necessary deck, fascia, and or framing;

7.1.3 Vendor must install new 1-1/2" aluminum drip edge around the perimeter of the cabin;

7.1.4 Vendor must install synthetic felt vapor barrier on roof deck;

7.1.4.1 Rhino roof U20 synthetic felt vapor barrier, or equal;

7.1.4.1.1 Thickness must be minimum 7 mils;

7.1.5 Vendor must install shingles;

7.1.5.1 Owens Corning Duration shingles, or equal;

7.1.5.1.1 Must be dimensional shingle;

7.1.5.1.2 Must have minimum 10-year algae resistance;

7.1.5.1.3 Agency must select color from manufacturer's available colors;

7.1.6 Vendor must remove wood shakes from chimney, reflash and install vinyl wood shake siding;

Project Name: Cabin Modernization-North Bend State Park

7.1.6.1 Norandex, Home Accents, Staggered Shake, or equal;

7.1.6.1.1 Must have fade protection warranty;

7.1.6.1.2 Agency must select color from manufacturer's available colors;

7.1.7 Vendor must replace chimney cap with stainless steel cap and pipe cap;

7.1.8 Vendor must install 6" seamless aluminum gutters with hidden hangers and gutter guards;

7.1.9 Vendor must install 3" x 4" downspout with drain adaptors;

7.1.10 Vendor must follow manufacturer's recommendations for installation;

8. Remove Existing and Replace Deck (Cabin 2 & 3);

8.1 Site conditions may require the Vendor to change the location of the steps. Deck may require built in removable frame to access water controls;

8.1.1 Vendor must field measure and remove existing decks, including steps and ramps;

8.1.2 Vendor must provide all material necessary;

8.1.3 Vendor must rebuild deck to same size and in same configuration;

8.1.4 All lumber used must be pressure treated and rated for outdoor use, lumber that meets the ground must be rated for "Ground Contact";

8.1.5 Footings should be installed or replaced as needed;

8.1.6 Fasteners should be compatible for use with treated lumber;

9. Kitchen Remodel (Cabin 2 & 3):

9.1 Remove Existing and Replace Kitchen Countertop;

9.1.1 Vendor must remove existing countertop;

9.1.2 Vendor must supply and install Du Pont Corian (Formerly Zodiaq) 2020 quartz kitchen countertop or equal;

9.1.2.1 Countertop must include predrilled hole (s) for specified faucet and drain;

9.1.2.2 Countertop must be prepped for undermount double basin stainless steel sink

Project Name: Cabin Modernization-North Bend State Park

- 9.1.2.3 Countertop must be a minimum of 1- $\frac{1}{4}$ " thick. Square edge;
- 9.1.2.4 Countertop must have minimum 4" integrated backsplash to be included and installed to existing configuration;
- 9.1.2.5 Vendor must field measure to ensure adequate coverage;
- 9.1.2.6 Vendor must follow manufacturer's recommendations for installation;

9.2 Remove Existing and Replace Kitchen Sink;

- 9.2.1 Vendor must supply and install 33-inch x 22-inch Double-basin, stainless steel undermount 2-hole sink;
 - 9.2.1.1 Sink must be stainless steel;
 - 9.2.1.2 Sink must be minimum 18 gauge;
 - 9.2.1.3 Sink must be a minimum of 8" deep, maximum of 12" deep;
 - 9.2.1.4 Sink must include basin grid;
 - 9.2.1.5 Sink must be corrosion resistant;
 - 9.2.1.6 All drains must be plumbed;
 - 9.2.1.7 Sink must include all necessary hardware and installed per manufacturer's recommendations;

9.3 Remove Existing and Replace Kitchen Faucet;

- 9.3.1 Vendor must supply and install a heavy duty, high arc, kitchen faucet with spray head;
- 9.3.2 Delta 9113-AR-DST Essa, or equal;
 - 9.3.2.1 Must be single handle pull down faucet;
 - 9.3.2.2 Finish to be selected by Agency;
 - 9.3.2.3 Faucet must have minimum flow rate of 1.80 GPM @ 60 PSI;
 - 9.3.2.4 Faucet must have minimum spout height of 15- $\frac{1}{4}$ "
 - 9.3.2.5 Faucet must have minimum spout length of 9- $\frac{1}{4}$ ";
 - 9.3.2.6 Faucet must have minimum deck thickness must be 2- $\frac{1}{2}$ ";
 - 9.3.2.7 Faucet must have magnetic docking spray head;

Project Name: Cabin Modernization-North Bend State Park

9.3.2.8 Faucet must be installed using manufacturer's installation recommendations;

9.3.2.8.1 Faucet must be fully plumbed to hot and cold water;

10. Bathroom Remodel (Cabin 2 ONLY – Both Bathrooms);

10.1 Remove Existing and Replace bathroom flooring;

10.1.1 Vendor must remove all existing bathroom fixtures and flooring to expose subfloor;

10.1.2 Vendor must repair any damaged bathroom subfloor;

10.1.3 Vendor must replace with new underlayment and install new tile;

10.1.4 Vendor must provide and install: Daltile, Fidenza, or equal glazed porcelain tile;

10.1.4.1 Tile must be minimum 5/16 in; thick;

10.1.4.2 Tile must have high resistance to abrasion and is suitable for heavy-duty residential and commercial floor installations;

10.1.4.3 Must have water absorption of less than 0;5% for indoor or outdoor use and is frost proof;

10.1.4.4 Dynamic Coefficient of Friction (DCOF) must be greater than or equal to 42 allows for application in most dry or wet areas including floors, walls, indoor or outdoor in freezing or non-freezing environments;

10.1.4.5 Vendor must follow manufacturer's recommendations for installation;

10.1.4.6 Vendor is required to field measure floor;

10.1.4.7 Pattern and color must be selected by Agency;

10.1.4.8 Grout color to match tile must be selected by Agency;

10.2 Remove Existing and Replace Vanity

10.2.1 Vendor must remove existing vanity;

Project Name: Cabin Modernization-North Bend State Park

10.2.2 Vendor must supply and install Shenandoah brand vanity base, or equal, to meet existing configuration;

10.2.2.1 Door style and hardware to be selected from Manufacturer's available selections;

10.2.2.2 Color to be selected by Agency from Manufacturer's available selections;

10.2.2.3 Vendor must follow manufacturer's recommendations for installation;

10.2.2.4 Must be minimum of 31-1/8" in height to match current configuration;

10.2.2.5 No shelf;

10.2.2.6 Door, 1 Panel;

10.2.2.7 Must be all plywood construction using 1/2" plywood;

10.2.2.8 Vendor is required to field measure to ensure fit;

10.3 Supply and Install Vanity top

10.3.1 Vendor must supply and install a built-in vanity top, with single, centered, rectangular undermount porcelain white sink and pre-drilled 4-inch-center hole to meet configuration of vanity base;

10.3.2 Vanity sink must meet the current configuration of existing sink;

10.3.3 Vendor must supply and install Du Pont Corian (Formerly Zodiaq) 2020 Quartz top, or equal;

10.3.3.1 Pattern to be selected from manufacturer's available patterns.
Top must be minimum 3/4" inch thick and must have square edge;

10.3.3.2 Vendor must follow manufacturer's recommendations for installation;

10.4 Supply and Install Sink Faucet;

10.4.1 Vendor must supply and install faucet;

10.4.1.1 Moen Banbury 4" center-set, 2 handle, high-arc faucet, or equal;

Project Name: Cabin Modernization-North Bend State Park

10.4.1.2 Faucet must have a rotating high-arc spout with a self-centering feature;

10.4.1.3 Faucet must have two handles;

10.4.1.4 Faucet must have minimum 1.2 GPM flow-rate;

10.4.1.5 Faucet must match specified bath hardware;

10.4.1.6 Finish must be selected by Agency;

10.5 Supply and Install Vanity mirror and light;

10.5.1 Vendor must remove existing vanity mirror and light;

10.5.2 Vendor must repair surface;

10.5.3 Vendor must supply and install, vanity mirror and light;

10.5.4 Vanity Mirror: 24 in. W x 30 in. L Framed Fog Free Wall Mirror;

10.5.4.1 Home Decorations Collection, or equal;

10.5.5 Vanity Light: allen + roth Hainsbrook 3-Light 25.98-in Model #B10072, or equal;

10.5.5.1 Finish to be selected by Agency;

10.5.5.2 Vanity light must have three lights;

10.5.5.3 Vanity light must be rated for damp installation;

10.5.5.4 Vanity light must be transitional in style;

10.5.5.5 Color must be selected by Agency;

10.5.5.6 Vendor must follow manufacturer's recommendations for installation;

10.6 Supply and Install Tub;

10.6.1 Vendor must remove existing tub;

10.6.2 Vendor must provide and install 60" left hand drain cast Iron bathtub,

10.6.2.1 Kohler Villager 60-in White Cast Iron or equal;

10.6.2.2 Vendor must follow manufacturer's recommendations for installation;

Project Name: Cabin Modernization-North Bend State Park

10.6.2.3 Vendor is required to field measure;

10.7 Supply and Install Tub Surround;

10.7.1 Vendor must prepare vertical surface per manufacturer's installation recommendations, supply and install ceramic tile on tub surround walls;

10.7.2 Vendor must provide and install: Daltile, Fidenza, or equal glazed porcelain, 6-inch x 6-inch tile and 3-inch x 12-inch bullnose;

10.7.2.1 Must be minimum 5/16 in. thick;

10.7.2.2 Must have water absorption of less than 0.5% for indoor or outdoor use and is frost proof;

10.7.2.3 Dynamic Coefficient of Friction (DCOF) must be greater than or equal to 42 allows for application in most dry or wet areas including floors, walls, indoor or outdoor in freezing or non-freezing environments;

10.7.2.4 Vendor must follow manufacturer's recommendations for installation;

10.7.2.5 Vendor is required to field measure walls;

10.7.2.6 Grout color to match tile must be selected by Agency;

10.8 Supply and Install Tub / Shower Fixture

10.8.1 Vendor must supply and install tub /shower fixture or equal.

10.8.2 Moen Banbury shower fixture;

10.8.2.1 Unit must provide temperature regulation and automatic anti-scald protection;

10.8.2.2 Unit must feature single handle controls both on/off activation and temperature setting;

10.8.2.3 Unit must include faceplate with ADA-compliant metal lever handle;

10.8.2.4 Unit must include single-function 1.7 GPM (gallons per minute) showerhead;

10.8.2.5 Vendor must follow manufacturer's recommendations for installation;

10.9 Supply and Install Towel Bars and hooks

Project Name: Cabin Modernization-North Bend State Park

- 10.9.1 Vendor must remove existing, repair surfaces, supply and install bathroom hardware;
- 10.9.2 Moen Banbury 4-Piece Bath, or equal including;
 - 10.9.2.1 toilet paper holder;
 - 10.9.2.2 24" towel rack;
 - 10.9.2.3 two-hook robe hook;
 - 10.9.2.4 hand towel ring;
- 10.9.3 Color must be selected by Agency;
- 10.9.4 Vendor must follow all manufacturer's recommendations for installation;
- 10.10 **Paint Walls in Bathroom;**
 - 10.10.1 Vendor must properly prepare walls for painting;
 - 10.10.1.1 Vendor must prepare walls to smooth surface and paint with semi-gloss PPG interior kitchen/bath paint;

**PROJECT SCOPE OF WORK
4-bedroom cabins: Cabin # 9**

11. Supply and Install Kitchen Countertops;

- 11.1.1 Vendor must remove existing countertop;
- 11.1.2 Vendor must supply and install Du Pont Corian (Formerly Zodiaq) 2020 quartz kitchen countertop or equal;
 - 11.1.2.1 Countertop must include predrilled hole (s) for specified faucet and drain;
 - 11.1.2.2 Countertop must be prepped for undermount double basin stainless steel sink
 - 11.1.2.3 Countertop must be a minimum of 1 ¼" thick. Square edge;
 - 11.1.2.4 Countertop must have minimum 4" integrated backsplash to be included and installed to existing configuration;
 - 11.1.2.5 Vendor must field measure to ensure adequate coverage;

Project Name: Cabin Modernization-North Bend State Park

11.1.2.6 Vendor must follow manufacturer's recommendations for installation;

12. Supply and Install Kitchen Sink;

12.1 Vendor must supply and install 33-inch x 22-inch Double-basin, stainless steel undermount 2-hole sink;

12.1.1 Sink must be stainless steel;

12.1.2 Sink must be minimum 18 gauge;

12.1.3 Sink must be a minimum of 8" deep, maximum of 12" deep;

12.1.4 Sink must include basin grid;

12.1.5 Sink must be corrosion resistant;

12.1.6 All drains must be plumbed;

12.1.7 Sink must include all necessary hardware and installed per manufacturer's recommendations;

13. Supply and Install Kitchen Faucet;

13.1 Vendor must supply and install a heavy duty, high arc, kitchen faucet with spray head;

13.1.1 Delta 9113-AR-DST Essa, or equal;

13.1.1.1 Must be single handle pull down faucet;

13.1.1.2 Finish to be selected by Agency;

13.1.1.3 Faucet must have minimum flow rate of 1.80 GPM @ 60 PSI;

13.1.1.4 Faucet must have minimum spout height of 15-1/4"

13.1.1.5 Faucet must have minimum spout length of 9- 1/4";

13.1.1.6 Faucet must have minimum deck thickness must be 2-1/2";

13.1.1.7 Faucet must have magnetic docking spray head;

13.1.1.8 Faucet must be installed using manufacturer's installation recommendations;

13.1.1.9 Faucet must be fully plumbed to hot and cold water;

Project Name: Cabin Modernization-North Bend State Park

PROJECT SCOPE OF WORK

Cabins #1, 2, 3, 4, 5, 6, 7, 8, 9

14. Added Alternate 1 - Install Agency Provided Dishwashers;

- 14.1 Vender must install a dishwasher provided by the Agency;
- 14.2 Vendor must remove the appropriate kitchen cabinet/s and add spacers or cabinet units as needed;
- 14.3 Vendor must supply and replace necessary finish trim work; Spacers or cabinet units must match existing cabinets in quality, style, and color;
- 14.4 Vendor must install the dishwasher as per manufacturer's recommendations including installing the appropriate plumbing connection;

15. Cabin Modernization-Quality Assurance

15.1 Quality Assurance

- 15.1.1 The Vendor shall use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the Work.
- 15.1.2 The Vendor shall provide any or all certifications, licenses, and labor necessary to assure obtaining the warranty.
- 15.1.3 The Vendor has the responsibility to protect the Agency's property and the property of others from damage due to weather or construction activities. The Vendor shall make any necessary provisions to prevent rain or other inclement weather from entering the structure.

15.2 Inspections

- 15.2.1 The authorized representatives and agents of the Division of Natural Resources shall be permitted to inspect all work, materials, payroll records of personnel, invoices of materials, and other relevant data and records.

15.3 Delivery, Storage, and Handling

- 15.3.1 Deliver the materials to the job site and store, in a safe area, out of the way of traffic, and stored up off the ground surface.
- 15.3.2 Use extreme care in off- loading of materials to prevent damage of materials and surrounding property.

Project Name: Cabin Modernization-North Bend State Park

15.4 Installation

15.4.1 The Vendor shall furnish all labor, equipment, and materials to perform the work.

15.4.2 Installation shall be in accordance with all Federal, State, and Municipal laws, codes, regulations, and ordinances that are pursuant to the Work. Comply with the provisions contained in the International Building Codes.

15.5 Other Materials

15.5.1 Vendor must provide necessary accessories, fittings, parts, hardware, mounting hardware, fasteners, materials, sealants, products, equipment and other work incidental to the installation to complete the work so as to function as intended. These are subject to the approval of the WVDNR.

15.5.2 Accessories, fittings, parts, hardware, mounting hardware, fasteners, materials, products, equipment, incidentals are to be from same manufacturer and commensurate quality as primary material, product, equipment for which they are incidental to, or be approved in writing by primary material, products, equipment for use.

15.6 Substitutions

15.6.1 Any substitution requests should be submitted by the technical question deadline.

16. Cabin Modernization-Site Conditions

16.1 Site Conditions

16.1.1 Vendor must keep the premises in a neat, safe, and orderly condition at all times. Remove debris and clean sidewalks, entries, exits, lawns, and parking areas at end of each work day.

16.1.2 Vendor must provide barriers, fencing, signs, and any other protection necessary to assure the safety of all visitors, staff, and contractors.

16.1.3 Vendor is to work with WVDNR personnel and visitors for a smooth operation. Professionalism and courteousness around WVDNR personnel and visitors shall be maintained at all times.

16.1.4 Means of egress from the Office building and parking lot, or access by emergency vehicles shall not be compromised.

Project Name: Cabin Modernization-North Bend State Park

- 16.1.5** The Vendor is responsible for protecting Work from inclement weather, snow, ice, rain, etc. Vendor is responsible for any snow removal, if necessary, in their work area.
- 16.1.6** Protect the lawns, plant materials, sidewalks, statues, signs, existing structures, cameras, wiring, etc. from any damage. Vendor is responsible for repairing or replacing any items that are damaged due to this work.
- 16.1.7** Bathroom facilities will be NOT available. Vendor to provide facilities.
- 16.1.8** Electric will be provided by the WVDNR during regular work hours for Work scope items only.

17. Cabin Modernization-Warranties

17.1 Warranties

- 17.1.1** Inspections, testing, etc. needed for warranty shall be the responsibility of the Vendor.

ADDENDUM ACKNOWLEDGEMENT FORM
SOLICITATION NO.: ARFQ DNR19*48

Instructions: Please acknowledge receipt of all addenda issued with this solicitation by completing this addendum acknowledgment form. Check the box next to each addendum received and sign below. Failure to acknowledge addenda may result in bid disqualification.

Acknowledgment: I hereby acknowledge receipt of the following addenda and have made the necessary revisions to my proposal, plans and/or specification, etc.

Addendum Numbers Received:

(Check the box next to each addendum received)

<input checked="" type="checkbox"/>	Addendum No. 1	<input type="checkbox"/>	Addendum No. 6
<input type="checkbox"/>	Addendum No. 2	<input type="checkbox"/>	Addendum No. 7
<input type="checkbox"/>	Addendum No. 3	<input type="checkbox"/>	Addendum No. 8
<input type="checkbox"/>	Addendum No. 4	<input type="checkbox"/>	Addendum No. 9
<input type="checkbox"/>	Addendum No. 5	<input type="checkbox"/>	Addendum No. 10

I understand that failure to confirm the receipt of addenda may be cause for rejection of this bid. I further understand that any verbal representation made or assumed to be made during any oral discussion held between Vendor's representatives and any state personnel is not binding. Only the information issued in writing and added to the specifications by an official addendum is binding.

Company

Authorized Signature

Date

NOTE: This addendum acknowledgment should be submitted with the bid to expedite document processing.